

Vendor: Cisco

Exam Code: 300-425

Exam Name: Designing Cisco Enterprise Wireless Networks (ENWLSD)

Version: 13.01

Q & As: 61

QUESTION 1

What is the recommended cell overlap when designing a wireless network for Cisco Hyperlocation?

- A. 20%
- B. 30%
- C. 40%
- D. 50%

Correct Answer: A

QUESTION 2

Which CLI command does an engineer use to validate that the redundancy peer of a Stateful Switchover pair of controllers is up and connected?

- A. rping
- B. ping
- C. eping
- D. mping

Correct Answer: B

QUESTION 3

An engineer must decide the cell overlap for a wireless voice deployment. Which Cisco measurement recommendation should be considered?

- A. The edge of the cell should be -67 dBm.
- B. The edge of the cell should be below 35 RSSI.
- C. The measurement should be done on the 2.4-GHz band.
- D. One AP should be deployed per 3000 square feet.

Correct Answer: A

QUESTION 4

Which UDP port numbers are used for exchange mobility packets in an AireOS wireless deployment?

- A. UDP 16666 for control plane, EoIP (IP protocol 97) for data plane
- B. UDP 16668 for control plane, UDP 16667 for data plane
- C. UDP 16667 for control plane, UDP 16666 for data plane
- D. UDP 16666 for control plane, UDP 16667 for data plane

Correct Answer: D

QUESTION 5

Which statement about AP failover priority for access points when configured with priority 1 or 4 is true?

A. When configured with priority 1, the access point is assigned with the highest priority level and it is marked as critical. This access point fails over before other access points with the lower priority when there is primary controller failure.

<u>300-425 Exam Dumps 300-425 PDF Dumps 300-425 VCE Dumps 300-425 Q&As</u>

- B. When configured with priority 4, the access point is assigned with the highest priority level and it is marked as critical. This access point fails over before other access points with the lower priority when there is primary controller failure.
- C. When configured with priority 4, the access point is assigned with the lowest priority level and it is marked as low. This access point fails over after other access points with the higher priority when there is primary controller failure.
- D. When configured with priority 1, the access point is assigned with the medium priority level and it is marked as medium. This access point fails over after other access points with the higher priority when there is primary controller failure.

Correct Answer: B

QUESTION 6

As part of a wireless site survey in a hospital, an engineer needs to identify potential Layer 1 interferers. In which two areas is the engineer most likely to find sources of 2.4 GHz and 5 GHz RF noise? (Choose two.)

- A. magnetic resonance imaging
- B. kitchen
- C. Gamma Knife radiation treatment
- D. X-ray radiography
- E. patient room

Correct Answer: BE

QUESTION 7

A wireless network consultant must assess an existing wireless LAN controller. Which section must the consultant check before replacing the old APs with APs that are IEEE 802.11ac-capable?

- A. number of AP licenses
- B. controller PSU
- C. throughput capacity
- D. software version

Correct Answer: A

QUESTION 8

A rapidly expanding company has tasked their network engineer with wirelessly connecting a new cubicle area with Cisco workgroup bridges until the wired network is complete. Each of 42 new users has a computer and VoIP phone. How many APs for workgroup bridging must be ordered to keep cost at a minimum while connecting all devices?

- A. 4
- B. 5
- C. 6
- D. 7

Correct Answer: A

QUESTION 9

<u>300-425 Exam Dumps</u> <u>300-425 PDF Dumps</u> <u>300-425 VCE Dumps</u> <u>300-425 Q&As</u> <u>https://www.ensurepass.com/300-425.html</u>

A network engineer is working on a design for a wireless network that must support data, voice, and location services. To support these services, which access point placement must the engineer use?

- A. corner only
- B. perimeter and corner
- C. perimeter only
- D. indoor and outdoor

Correct Answer: C

QUESTION 10

An engineer has successfully configured high availability and SSO using two Cisco 5508 Wireless LAN Controllers. The engineer can access the Active Primary WLC, but the Secondary Standby WLC is not accessible. Which two methods allow access to the standby unit? (Choose two.)

- A. via the console connection
- B. SSH to the redundancy management interface of the primary WLC
- C. SSH to the service port interface
- D. SSH to the virtual interface of the secondary WLC
- E. SSH to the management interface of the primary WLC

Correct Answer: AC

QUESTION 11

An engineer must create data-link redundancy for the company's Cisco Wireless LAN Controller. The engineer has decided to configure LAG-based redundancy instead of port-based redundancy. Which three features of LAG-based redundancy influenced this decision? (Choose three.)

- A. Packets are always sent out on the same port they are received on.
- B. All interface traffic passes as long as one port is up.
- C. The same port has multiple untagged dynamics interfaces.
- D. Interface connection to two separate nonstacked switches is available.
- E. Full bandwidth of all links is available.
- F. Ports are grouped into multiple LAGs.

Correct Answer: ABF

QUESTION 12

Clustering Cisco WLCs into a single RF group enables the RRM algorithms to scale beyond the capabilities of a single Cisco WLC. How many WLC and APs in an RF group can the controller software scale up to in WLC release 8.9 depending on the platform?

- A. up to 20 WLCs and 1000 APs
- B. up to 20 WLCs and 3000 APs
- C. up to 20 WLCs and 4000 APs
- D. up to 20 WLCs and 6000 APs

Correct Answer: D

QUESTION 13

A company wants to replace its existing PBX system with a new VoIP System that will include wireless IP phones. The CIO has concerns about whether the company's existing wireless network can support the new system. Which tool in Cisco Prime can help ensure that the current network will support the new phone system?

- A. Location Readiness
- B. Site Calibration
- C. Map Editor
- D. Voice Readiness

Correct Answer: D

QUESTION 14

An engineer must speed up the reauthentication delays that are being experienced on the wireless infrastructure by deploying a key-caching mechanism. Which mechanism must be configured?

- A. PEAP
- B. FT
- C. PMF
- D. GTK-randomization

Correct Answer: B

QUESTION 15

A wireless engineer is utilizing the voice readiness tool in Cisco Prime for a customer that wants to deploy Cisco IP phones. Which dBm range is the network inspected against?

- A. -78 to -65 dBm
- B. -72 to -67 dBm
- C. -85 to -65 dBm
- D. -85 to -67 dBm

Correct Answer: D

QUESTION 16

An engineer is designing a wireless deployment for a university auditorium. Which two features can be used to help deal with the issues introduced by high AP count? (Choose two.)

- A. TSPEC
- B. RXSOP
- C. TPC
- D. LSS
- E. DFS

Correct Answer: CE

QUESTION 17

A company has 10 access point licenses available on their backup Cisco WLC and their primary Cisco WLC is at full capacity, 5 access points are set to high failover priority and 7 access points

<u>300-425 Exam Dumps 300-425 PDF Dumps 300-425 VCE Dumps 300-425 Q&As</u>

https://www.ensurepass.com/300-425.html